

Table 2-6

**MONITORING WELL AND PIEZOMETER CONSTRUCTION DATA
CHAMPAIGN MGP SITE
CHAMPAIGN, ILLINOIS**

MW / PZ NUMBER	DATE INSTALLED	TOTAL DEPTH FEET (BGS)	CONSTRUCTION TYPE	SCREEN INTERVAL FEET (BGS)	SURFACE ELEVATION
UMW-101	12/04/90	26.5	PVC-2"	14.0 - 26.5	736.4
UMW-102	11/28/90	22.4	PVC-2"	6.0 - 22.4	737.8
UMW-103	11/30/90	21.0	PVC-2"	7.0 - 21.0	736.5
UMW-104	11/27/90	23.5	PVC-2"	7.8 - 23.5	736.5
UMW-105	12/05/90	19.7	PVC-2"	7.7 - 19.7	737.8
UMW-106	11/29/90	21.0	PVC-2"	7.0 - 21.0	737.7
UMW-107	12/05/90	19.7	PVC-2"	7.5 - 19.7	737.3
UMW-108	11/29/90	16.0	PVC-2"	3.8 - 16.0	737.2
UMW-109	12/17/91	20.0	SS-2"	9.0 - 20.0	735.7
UMW-110	12/04/90	21.0	PVC-2"	8.3 - 21.0	737.4
UMW-111	12/07/90	19.8	SS-2"	7.5 - 19.8	736.1
UMW-112	12/07/90	20.0	SS-2"	7.0 - 20.0	737.9
UMW-113	12/11/91	20.5	SS-2"	8.0 - 20.5	738.0
UMW-114	12/12/91	21.0	SS-2"	8.0 - 21.0	738.2
UMW-115	12/12/91	21.0	SS-2"	8.0 - 21.0	738.1
UMW-116	12/11/91	20.0	SS-2"	8.0 - 20.0	737.2
UMW-401	12/05/90	175.0	PVC-2"	138.5 - 175.0	738.7
UMW-402	12/03/90	176.5	PVC-2"	134.0 - 170.0	737.6
UMW-403	12/07/90	170.0	PVC/SS-2"	128.0 - 170.0	737.5
UPZ-101	12/06/90	8.0	PVC-1"	4.0 - 8.0	738.2
UPZ-201	12/06/90	16.0	PVC-1"	12.0 - 16.0	738.2
UPZ-301	12/06/90	25.0	PVC-1"	21.0 - 25.0	738.2
UPZ-102	12/13/91	10.5	PVC-1"	4.0 - 10.5	738.0
UPZ-202	12/13/91	25.5	PVC-1"	19.5 - 25.5	738.0
UPZ-302	12/13/91	35.0	PVC-1"	29.0 - 35.0	738.0
UPZ-103	12/06/90	9.5	PVC-1"	4.5 - 9.5	737.4
UPZ-203	12/06/90	15.0	PVC-1"	11.5 - 15.0	737.4
UPZ-104	12/14/91	11.0	PVC-1"	4.0 - 11.0	738.7
UPZ-204	12/14/90	24.0	PVC-1"	17.0 - 24.0	738.7
UPZ-105	12/15/91	10.5	PVC-1"	4.0 - 10.5	738.6
UPZ-205	12/15/91	20.5	PVC-1"	14.0 - 20.5	738.6
UPZ-106	12/14/91	13.5	PVC-1"	7.0 - 13.5	738.4
UPZ-206	12/14/91	23.5	PVC-1"	17.0 - 23.5	738.4
UPZ-107	12/15/91	12.5	PVC-1"	3.0 - 12.5	737.9
UPZ-108	12/16/91	15.5	PVC-1"	4.0 - 15.5	739.3

PVC - Polyvinyl Chloride.

SS - Stainless Steel.

BLS - Below Land Surface.